

म०प्र०राज्य कृषि विपणन बोर्ड
26, किसान भवन, अरेरा हिल्स, भोपाल

क./बोर्ड/निर्माण/19-20/745

भोपाल, दिनांक 30/04/2019

प्रति,


संयुक्त संचालक/उपसंचालक/कार्यपालन यंत्री
म०प्र०राज्य कृषि विपणन बोर्ड
आंचलिक कार्यालय/तकनीकी संभाग(समस्त)

विषय:- मंडी/उपमंडी प्रांगणों में वृक्षारोपण कार्य के संबंध में।

—000—

विषयांतर्गत मंडी/उपमंडी प्रांगणों में वृक्षारोपण का कार्य प्रतिवर्ष कराया जाता है। वृक्षारोपण हेतु निम्नानुसार प्रक्रिया निर्धारित की जाती है।

- (1) मंडी/उपमंडी के ले-आउट प्लान में वृक्षारोपण हेतु स्थान निर्धारित किये जायें, जिसमें भविष्य के मंडी के विकास कार्यों का भी ध्यान रखा जावे। वृक्षारोपण का कार्य कराते समय पर ध्यान रखा जावे कि भविष्य में इसके कारण किसी प्रकार की असुविधा तो नहीं होगी।
- (2) मई के माह में वृक्षारोपण हेतु आवश्यकतानुसार गड्डे खुदवा लिये जाये।
- (3) गड्डों में आवश्यकतानुसार गोबर की खाद डाली जाये, एवं वर्षाकाल प्रारंभ होने तक गड्डे खुले रखे जाये।
- (4) वर्षाकाल प्रारंभ होने के 10-15 दिन के उपरांत वृक्षारोपण का कार्य प्रारंभ कराया जावे।
- (5) वृक्षारोपण में लगाये गये पौधों की सुरक्षा के लिये ट्री गार्ड लगाये जावे।
- (6) वृक्ष लगाने के उपरांत एक अस्थाई माली/श्रमिक उद्यानिकी विभाग के माध्यम से वृक्षों की देख रेख हेतु रखा जावे।
- (7) मंडी/उपमंडी प्रांगणों में फलदार वृक्ष न लगायें जावे।
- (8) वृक्षों का चयन ऐसा किया जाये, जिनसे गर्मी में भी हरियाली रहे जैसे नीम, शीशम, करंज एवं सप्तपर्णी आदि।
- (9) वृक्षारोपण कार्य हेतु कमशः 50 एवं 100 वृक्षों के लिये अनुमानक तैयार कर प्रेषित किया जा रहा है।
- (10) मंडी समिति बजट प्रावधान अनुसार वृक्षारोपण का कार्य कराए।
- (11) वृक्षारोपण हेतु वृक्ष शासकीय पौध शालाओं से (वन विभाग - हार्टिकल्चर) कय किये जावे।


प्रबंध संचालक


म०प्र०राज्य कृषि विपणन बोर्ड,
भोपाल

क./बोर्ड/निर्माण/19-20/746

भोपाल, दिनांक 30/04/2019

प्रतिलिपि:-सूचनार्थ एवं आवश्यक कार्यवाही हेतु:-

- (1) अपर संचालक, (समस्त) म.प्र.राज्य कृषि विपणन बोर्ड मुख्यालय, भोपाल।
- (2) अधीक्षण यंत्री, (समस्त) म.प्र.राज्य कृषि विपणन बोर्ड मुख्यालय, भोपाल।
- (3) कार्यपालन यंत्री, (समस्त) म.प्र.राज्य कृषि विपणन बोर्ड मुख्यालय, भोपाल।
- (4) सचिव, कृषि उपज मंडी समिति.....(समस्त) की ओर उपरोक्तानुसार कार्यवाही की जाना सुनिश्चित करें।



एवंध संचालक

म0प्र0राज्य कृषि विपणन बोर्ड,
भोपाल

Detailed Bill of plantation work in mandi (50 Plants)

Sl. No.	Particulars of item	Nos.	Length	Width	Height	Quantity	Unit	Rate	Amount
1	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2:1 by volume (2 parts of stacked volume of earth after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%) flooding with water, dressing including removal of rubbish and surplus earth, if any with all leads and lifts (cost of manure, sludge or extra good earth if needed to be paid for separately) :	3	4	5	6	7	8	9	10
1	23.14.2 Holes 60 cm dia. and 60 cm deep	50				50.00	Each	61.2	3060
				Total Quantity		50.00			
2	Supplying and stacking of well decayed cow dung manure at site including royalty and carriage upto 1 km (Cow dung manure measured in stacks will reduced by 8% for Payment).								
	23.21 total volume of digging	50	3.14	0.60	0.60	8.48			
	20 % of total digged soil					1.70			
	Volume of cow dung to be paid					1.56			
				Total Quantity		1.56	Cum	717.3	1119
4	Providing and fixing M. S. tree guard 45 cm square in plan, height 1.20 metre above ground level and 0.40 metre below ground level. The vertical members shall consist of four nos. angle iron of size 25x25x3 mm, 1.8 m long, one at each corner and 8 nos. flat iron of size 25x3 mm, 1.2 m long. The vertical members shall be welded to 4 nos. 25x6 mm M. S. flats placed horizontally around the vertical member of the cage. One name plate of 1 mm thick M.S. sheet of size 250x100 mm shall be welded to the tree guard near the middle height and lettered 'PWD/ any other approved name. The tree guard shall be fixed to the ground by making suitable holes and by embedding four corners leg in the ground, including refilling the earth, compaction etc. complete. The tree guard shall be painted with two or more coats of synthetic enamel paint of approved brand and manufacture over a coat of primer, complete in all respect								
		50				50.00	Each	1426.5	71325
	TOTAL AMOUNT ON SOR			Total Quantity		50.00	Each		
	add 12% GST							75504	
	GROSS AMOUNT							90660	
	add 2% contingencies							84564	
	GRAND TOTAL							1691	
	Cost per plant							86256	1725

Singh

Estimate
Detailed of plantation work in mandi (100 Plant)

Sl. No.	Particulars of item	Nos.	Length	Width	Height	Quantity	Unit	Rate	Amount
1	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2:1 by volume (2 parts of stacked volume of earth after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%) flooding with water, dressing including removal of rubbish and surplus earth, if any with all leads and lifts (cost of manure, sludge or extra good earth if needed to be paid for separately) :	3	4	5	6	7	8	9	10
1	23.14.2 Holes 60 cm dia. and 60 cm deep.	100				100.00	Each	61.2	6120
						Total Quantity			
2	Supplying and stacking of well decayed cow dung manure at site including royalty and carriage upto 1 km (Cow dung manure measured in stacks will reduced by 8% for Payment).								
	23.21 total volume of digging	100	3.14	0.60	0.60	16.96			
	20 % of total digged soil					3.39			
	Volume of cow dung to be paid					3.12			
						Total Quantity	Cum	717.3	2238
4	Providing and fixing M. S. tree guard 45 cm square in plan, height 1.20 metre above ground level and 0.40 metre below ground level. The vertical members shall consist of four nos. angle iron of size 25x25x3 mm, 1.8 m long, one at each corner and 8 nos. flat iron of size 25x3 mm, 1.2 m long. The vertical members shall be welded to 4 nos. 25x6 mm M. S. flats placed horizontally around the vertical member of the cage. One name plate of 1 mm thick M.S. sheet of size 250x100 mm shall be welded to the tree guard near the middle height and lettered PWD/ any other approved name. The tree guard shall be fixed to the ground by making suitable holes and by embedding four corners leg in the ground, including refilling the earth, compaction etc. complete. The tree guard shall be painted with two or more coats of synthetic enamel paint of approved brand and manufacture over a coat of primer, complete in all respect	100				100.00	Each	1426.5	142650
	23.22					Total Quantity			
	TOTAL AMOUNT ON SOR					100.00	Each	151008	151008
	add 12% GST							18121	18121
	GROSS AMOUNT							169129	169129
	add 2% contingencies							3383	3383
	GRAND TOTAL							172511	172511
	Cost per plant							1725	1725

Shery